

STATE OF KANSAS  
OIL CORPORATION COMMISSION  
S. Market, Room 2078  
Tulsa, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-009-03399-00-00  
API NUMBER Comp. 6-12-46

LEASE NAME Riemann

WELL NUMBER 7

4280  
990 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 25 TWP. 16 RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed 6-12-46

Plugging Commenced 1-9-04

Plugging Completed 1-12-04

RECEIVED

FEB 03 2004

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR ROBINOWITZ OIL COMPANY

ADDRESS 7130 S. Lewis, Suite 910 Tulsa, OK. 74136

PHONE (918) 481-7130 OPERATOR'S LICENSE NO. 6883

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on (date)

Pat Staab (KCC District Agent's Name).

ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3344'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surf			727	10" 3/4	777'	None
Prod			3331	5-1/2"	3331'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from feet to feet each side. Perforated well @1475' and 775'. Ran in 1500' of 2-3/8" tubing, pumped 190 sacks cement with 500# hulls and circulated to surface. Layed down tubing, hooked onto 5-1/2" casing and pumped 200 sacks cement with 100# hulls & circulated out backside. Shut in backside and pumped 70 sacks cement. Used 60/40 pos, 10% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robinowitz Oil Company

STATE OF Kansas COUNTY OF Rice, SS.

Mike Kelso

(Employee of Operator) or (Operator)

Above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 2nd. day of February, 2004

[Signature]  
Notary Public

My Commission Expires:



Form 07  
Revised 05-