

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R. -82-3-117

API NUMBER 15-077-20555-00-00

LEASE NAME Hostetler

WELL NUMBER 2

4950 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 19 TWP. 31 RGE. 6  E  W

COUNTY Harper

Date Well Completed 2-4-1980

Plugging Commenced 1/15/04

Plugging Completed 1/14/04

<sup>09</sup>  
1/13/04 (date)

LEASE OPERATOR McCoy Petroleum Corp.

ADDRESS 8080 E Central, Suite 300, Wichita, Ks 67206

PHONE # (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_

by Doug Louis (KCC District Agent's Name),

Is ACO-I filed? yes If not, Is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4840'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	318'	none
Production				5 1/2"	4837'	3220'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Quality Well Service, Inc. plugged well as follows: Sand at 4571', bail 5 sacks cement. Rip pipe at 3345', 3220', work free and pull to 600'. Pulled to 1300', pump 35 sacks cement. Pull to 700', pump 35 sacks cement. Pull to 350', circulate cement to surface with 130 sacks cement. Pull rest of pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 401 West Main, Lyons, Ks 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES McCoy Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick ss.

Scott Hampel (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott Hampel

(Address) 8080 E Central, Ste. 300, Wichita KS 67206

SUBSCRIBED AND SWORN TO before me this 30th day of January, 20 04

Susan Brady  
Notary Public

My Commission Expires 11-4-07

