

STATE CORPORATION COMMISSION OF KANSAS
 OIL & GAS CONSERVATION DIVISION
 130 S. MARKET, - ROOM 2078
 WICHITA, KANSAS 67202-3802

API NUMBER 15-055-21808 ~~00~~ 00
 LEASE NAME Wilcox
 WELL NUMBER Wilcox 17-2

WELL PLUGGING RECORD K.A.R.-82-3-117

Type or Print Notice: Fill out completely and return to Cons Div office within 30 days

Lease Operator PETROSANTANDER (USA) INC
 Address 6363 Woodway #350,
 Address Houston, Texas 77057
 Phone 713-784-8700
 Operators License 32198
 Character of Well D/A (Oil, Gas, D&A, SWD, Water Supply)

The plugging proposal was approved on 01-15-2004 (date)
 by Kevin Strubbe (KCC District Agent's Name)
 Is ACO-1 filed? Enclosed

Show depth and thickness of all water, oil and gas formations.

300 feet from N/S Section Line
1650 feet from E/W Section Line
 SEC 17 TWP 23S RGE 30 (NW)
 COUNTY FINNEY
 Date Well Completed 01-14-2004
 Plugging Commenced 01-15-2004
 Plugging Completed 01-15-2004
 Producing Formation _____
 Depth to Top _____ **RECEIVED**
 Depth to Bottom _____ **FEB 02 2004**
 T.D. 4900'
 If not is well log attached? KCC WICHITA

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	509'	8-5/8"	11 jts 24# 509	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Filled with heavy mud, 1st Plug @ 2100' w/50 sks,
 2nd Plug @ 1150' w/80 sks
 3rd Plug @ 520' w/40 sks
 4th Plug @ 40' w/10 sks Total 180 sks 60-40 Poz 6% gel, 1/4# floseal

Name of Plugging Contractor Allied Cementing Co Inc Cheyenne License No. N/A 5382
 Address 24 Sth Lincoln, Russell, Kansas 67665 Drilling Co 3728 W Jones Ave
Gardencity


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PETROSANTANDER
 STATE OF TEXAS COUNTY OF HARRIS, ss.
JASON SIZEMORE (Employee of Operator) or (Operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature _____ Address 6363 Woodway #350, Houston, Texas 77057

SUBSCRIBED AND SWORN TO before me this 29th day of January, 2004

Notary Public Alan Edwards
 My Commission Expires 19th Sept. 2007



Bm