

STATE OF KANSAS
OIL AND GAS COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-135-21714-00-00

LEASE NAME Stutz "B"

WELL NUMBER 3

660 Ft. from N Section Line

460 Ft. from E Section Line

SEC. 7 TWP. 17S RGE. 25W (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 1-23-04

Plugging Completed 1-23-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Double Eagle Exploration, Inc.

ADDRESS 221 S. Broadway Suite 310, Wichita, Ks. 67202

PHONE (316) 264-0422 OPERATOR'S LICENSE NO. 6009

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

RECEIVED
FEB 05 2004
KCC WICHITA

A plugging proposal was approved on _____ (date)

Mike Maier

(KCC District Agent's Name)

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4513'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
			<u>306</u>	<u>8-5/8"</u>	<u>306'</u>	<u>None</u>
			<u>4508</u>	<u>4-1/2"</u>	<u>4508'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from _____ feet to _____ feet each side. Well bridged off @1400'. Ran tubing to 1300' and set packer, pressured up on backside, held. Ran tubing to 1200', ran 35 sacks common, pulled 5 jts. tubing, set packer and let cement set. Pressured up on plug, pulled tubing. Perforated 4-1/2" casing @1100', pumped 70 sacks cement, 90 sacks cement w/200# hulls, tied onto backside and pumped 150 sacks cement, 60/40 pos, 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Double Eagle Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

Do hereby certify that the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed therewith, and that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 4th day of February, 2004

[Signature]
Notary Public

My Commission Expires: _____



Form CP
Revised 05-