

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 200
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-077-21399-00-00

LEASE NAME Wurm A

RECEIVED
FEB 02 2004
KCC WICHITA

TYPE OR PRINT
NOTICE- Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-15

3300 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR McCoy Petroleum Corp.

SEC. 15 TWP. 34s RGE. 8 E W

ADDRESS 8080 E Central, Suite 300, Wichita, Ks 67206

COUNTY Harper

PHONE # (316) 636-2737 OPERATORS LICENSE NO. 5003

Date Well Completed 5/25/01

Character of Well oil

Plugging Commenced 1/14/04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1/15/04

The plugging proposal was approved on 1/14/04 (date)

by Doug Louis (KCC District Agent's Name),

Is ACO-I filed? yes If not, Is well log attached? yes

Producing Formation Mississippian Warsaw Depth to Top 4706' Bottom 4720' T.D. 4720'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8	267'	none
Production				4 1/2	4706'	3400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Quality Well Service, Inc. plugged well as follows: Sand at 4626', bail 4 sacks cement. Rip pipe at 3640', 3400', work free and pull to 1350', pump 35 sacks cement. Pull to 900', pump 35 sacks cement. Pull to 320', circulate cement to surface with 130 sacks cement. Pull rest of pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 401 West Main, Lyons, Ks 67554


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES McCoy Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick ss.

Scott Hampel (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott Hampel

(Address) 8080 E Central, Ste. 300, Wichita KS 67206



SUBSCRIBED AND SWORN TO before me this 30th day of January, 20 04

Susan Brady
Notary Public

My Commission Expires 11-4-07