

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 -S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-065-22955-0000

LEASE NAME Martha

WELL NUMBER 1

1,380 Ft. from N Section Line

2,080 Ft. from W Section Line

SEC. 22 TWP. 8 RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed 1-27-04

Plugging Commenced 1-27-04

Plugging Completed 1-28-04

FEB 05 2004  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pioneer Resources

ADDRESS 177 W. Limestone Road, Phillipsburg, KS

PHONE (785) 543-5556 OPERATORS LICENSE NO. 67661  
32016

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-27-04 (date)

by Pat Stabb (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3,725'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand</u>			<u>218</u>	<u>8 5/8"</u>	<u>218'</u>	<u>Cmtd. w/175 sax</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Push plug to 1,878', spot 25 sax cement on plug thru drill pipe. Push plug to 1,046', spot 100 sax cement on plug thru drill pipe. Push plug to 270', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pioneer Resources

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor


above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 2004

My Commission Expires:



Ruth Phillips  
Notary Public




# Shields

Russell, Kansas

## WELL LOG

Operator: Pioneer Resources  
 Well: Martha #1  
 Commenced: January 22, 2004  
 Completed: January 28, 2004  
 Contractor: Shields Drilling Co.

Well Description: 1,380' FNL, 2,080' FWL  
 Sec. 22-8S-23W  
 Graham Co., KS



### CASING RECORD

Size	Run	Pulled
8 5/8"	218'	Cmtd. w/175 sax

Elevation: 2,196' KB

Treatment:

Production: D & A

Tops:

**RECEIVED**  
**FEB 05 2004**  
**KCC WICHITA**

..... Figures Indicate Bottom of Formations .....

Clay, sand, shale	75'
Shale	221'
Shale & sand	1,862'
Anhydrite	1,893'
Shale	2,380'
Shale & sand	2,622'
Shale	3,240'
Shale & lime	3,650'
Lime	3,725' RTD

Notes