

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-21062-00-00

LEASE NAME Milburn A

WELL NUMBER 1

2050 Ft. from S. Section Line

660 Ft. from E Section Line

SEC. 31 TWP. 31 RGE. 39 (W)

COUNTY Morton 1-3091

Date Well Completed 8-23-91

Plugging Commenced 1-8-04

Plugging Completed 1-9-04

RECEIVED

FEB 04 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oxy USA, Inc

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE(S) (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-7-04 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5783 Bottom 5851 T.O. 6001'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Cond</u>			<u>41</u>	<u>20</u>	<u>41</u>	<u>-</u>
<u>Surf</u>			<u>1729</u>	<u>8 3/8</u>	<u>1729</u>	<u>-</u>
<u>Prod</u>			<u>6000</u>	<u>5 1/2</u>	<u>6000</u>	<u>1243</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set
CIBP + 25x 5750 to 5730 Mud spacer to 1800 25 5x cmt 1800 to 1600 in 5 1/2
shot 5 1/2 Circ hole w/mud & mixed 30 5x 1240 to 1140 30 5x 500 to 400
10 5x 40-0 Cut off & capped 8 3/8 3 ft. below Gil.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.


STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed in
the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 29th day of Jan, 2004



Anita Peterson
Notary Public

Commission Expires: Oct 1, 2005