

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-081-20287-00-01

LEASE NAME Moody C

WELL NUMBER 3

4620 Ft. from S. Section Line

600 Ft. from E Section Line

SEC. 3 TWP. 29 RGE. 34 (E or W)

COUNTY Haskell

Date Well Completed 1-14-91

Plugging Commenced 1-16-04

Plugging Completed 1-19-04

RECEIVED

FEB 04 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well oil

(OIL) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-14-04 12-16-03 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top 4175 Bottom 4184 T.D. 5500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Cond</u>				<u>20</u>	<u>30</u>	<u>-</u>
<u>surf.</u>				<u>8 3/4</u>	<u>1772</u>	<u>-</u>
<u>Prod</u>			<u>3044</u>	<u>5 1/2</u>	<u>5499</u>	<u>1916</u>
<u>CIP</u>			<u>4390</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each so

Mixed 300 lb. hulls & 25 5x cmt. to plug perfs from 4175 to 3975. Pull 5 1/2 to 1800. Circ hole w/mud 50 5x 1800 to 1650 30 5x 600 to 500 10 5x 40 to 0
Cut off & capped 8 3/4 5-ft. below Gil.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.


Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 30th day of Jan, 19 2004

Anita Peterson
Notary Public



Expires: Oct. 1, 2005