

RECEIVED

FEB 04 2004

KCC WICHITA

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas Blvd Box 2528 Liberal, KS 67905

PHONE(S) (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-22-04 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Council Grove Depth to Top 2794' Bottom 2824' T.D. 5000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>1763</u>	<u>8 5/8</u>	<u>1763</u>	<u>-</u>
<u>Prod</u>			<u>4974</u>	<u>5 1/2</u>	<u>4974</u>	<u>-</u>
<u>C.B.P</u>			<u>3300</u>	<u>B</u>		
<u>M.S.C.C.</u>			<u>3319</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.
Mixed 300 lb. hulls & 25 sx cmt to plug perfs from 2794 to 2594,
pumped mud spacer to 1800, mixed 80 sx 1800 to 1100, mud spacer
to 600, mixed 70 sx 600 to 0. Mixed 5 sx down annulus from 30 to 0.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 30th day of Jan, 2004

Anita Peterson
 Notary Public

My Commission Expires: Oct. 1, 2005
 ANITA PETERSON
 MY COMMISSION EXPIRES
 October 1, 2005

