

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-10019-60-00

LEASE NAME Knoeber A

WELL NUMBER 1

4030 Ft. from S. Section Line

4030 Ft. from E Section Line

SEC. 33 TWP. 32 RGE. 42 (W)

COUNTY Morton

Date Well Completed 12-19-55

Plugging Commenced 1-7-04

Plugging Completed 1-7-04

RECEIVED
FEB 04 2004
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS 67905

PHONE (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, ~~Gas~~, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-6-04 (date)
by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Topeka Depth to Top 2932 Bottom 3108 T.D. 3210'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>600</u>	<u>8 5/8</u>	<u>600</u>	<u>-</u>
<u>Prod</u>			<u>3203</u>	<u>5 1/2</u>	<u>3203</u>	<u>877</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each so
Mixed 600 lb. hulls & 25 sx cmt. to plug perfs from 2932 to 2732. Pull 5 1/2
to 630 Circ. hole w/mud. 50 sx cmt. 630 to 480 10 sx 40 to 0 Cut off
& capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.


STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed th
the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 29th day of Jan., 1/29/2004



Anita Peterson
Notary Public

Commission Expires: Oct. 1, 2005