

LEASE NAME MLA Gillespie A

RECEIVED

WELL NUMBER 3

FEB 04 2004

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

3300 Ft. from S. Section Line

660 Ft. from <sup>W</sup> Section Line

KCC WICHITA

SEC. 3 TWP. 32 RGE. 39 (E) or (M)

COUNTY Stevens 7-11-95

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONES (201) 629-4200 OPERATORS LICENSE NO. 5447

Date Well Completed 9-13-95

Character of Well Gas

Plugging Commenced 1-9-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-9-04

The plugging proposal was approved on 1-8-04 (date)

by Jim Holland (KCC District Agent's Name).

is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mcrow Depth to Top 5490' Bottom 5496' T.D. 6170'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>1703</u>	<u>8 5/8</u>	<u>1703</u>	<u>-</u>
<u>Prod</u>			<u>5656</u>	<u>4 1/2</u>	<u>5656</u>	<u>-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so Mixed 200 lb hulls & 20 5x cmt to plug perfs from 5490 to 5290, mud spacer to 1750, 20 5x cmt 1750 to 1550, mud spacer to 675, 63 5x cmt, 675 to 0 Mixed 5 5x cmt down annulus from 30 to 0. Cut off 8 5/8 & 5 1/2 & capped 8 5/8 5 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.


Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 29th day of Jan, 2004

Anita Peterson  
 Notary Public



ANITA PETERSON  
 MY COMMISSION EXPIRES  
 October 1, 2005

Expires: Oct. 1, 2005