

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-21215-00-01
Spot: N2SWNW Sec/Twnshp/Rge: 25-30S-35W
3450 feet from S Section Line, 4620 feet from E Section Line
Lease Name: MLP QUIETT A Well #: 1
County: GRANT Total Vertical Depth: 5750 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

CIBP Size: feet: 5460 WITH 2 SX CMT
COND Size: 20 feet: 70 UNKNOWN
MSCC Size: feet: 2911 WITH 435 SX CMT
PROD Size: 5.5 feet: 5749 WITH 945 SX CMT
SURF Size: 8.625 feet: 1635 WITH 725 SX CMT

#18688

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/16/2004 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1700' WITH 25 SX CMT. PLUG AT 500' WITH 60 SX CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2004 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5450'. PUMP 300# HULLS & 25 SX CMT. DISPLACE WITH 80 BBL MUD. 1ST PLUG PUMP MUD SPACER TO 1700 & PUMP 25 SX CMT AT 1700'. PUMP 18 BBL MUD SPACER TO 500'. CHECK WIRELINE. 2ND PLUG PUMP 60 SX CMT FROM 500' TO SURFACE. PRESSURE TO 600 PSIG & SHUT IN. PUMP 6 SX CMT DOWN BACKSIDE. PRESSURE TO 500 PSIG & SHUT IN.

Perfs:

Top	Bot	Thru	Comments
5479	5489	CSG	
5216	5229	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 10 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
JAN 29 2004
KCC Dodge City

Signed

Jim Holland (TECHNICIAN)

INVOICED

DATE

INV. NO.

2-11-04
2004061165

Form CP 23