

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20349-00-01
Spot: NWNW Sec/Twnshp/Rge: 25-30S-34W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: SCHNELLBACHER E Well #: 1
County: HASKELL Total Vertical Depth: 5650 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

CIBP Size: feet: 5394
CIBP Size: feet: 5500 WITH 1 SX CMT
COND Size: 20 feet: 20 UNKNOWN
PROD Size: 5.5 feet: 5643 WITH 175 SX CMT
SURF Size: 8.625 feet: 1808 WITH 800 SX CMT

#183⁶³

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/27/2004 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1830' WITH 50 SX CMT. PLUG AT 650' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: PARTIAL
Date/Time Plugging Completed: 01/28/2004 10:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CASING LEAK 4071-4103'. PUMP 300# HULLS FOLLOWED BY 25 SX CMT. DISPLACE BOTTOM WITH 100 BBL MUD. PRESSURE TO 700 PSIG. 1ST PLUG AT 1774' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5554	5557		
5427	5431		
5404	5409		
4776	4784		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 10 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1774' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
JAN 29 2004
KCC Dodge City

Signed

Jim Holland PART II
INVOICED (TECHNICIAN)

DATE 2-11-04

WT. NO. 2004061165

Form 29-273