

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21658-00-00  
Spot: SWNESENE Sec/Twnshp/Rge: 8-32S-34W  
3410 feet from S Section Line, 412 feet from E Section Line  
Lease Name: SLOAN A Well #: 3  
County: SEWARD Total Vertical Depth: 6400 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: PO BOX 27570 5 E GREENWAY PLZ  
HOUSTON, TX 77227

CIBP Size: feet: 6224  
MSCC Size: feet: 3071 CMT TO SURFACE  
PROD Size: 5.5 feet: 6372 WITH 600 SX CMT  
SURF Size: 8.625 feet: 1741 WITH 510 SX CMT

#208<sup>00</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2004 1:00 PM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS WITH 25 SX CMT. MUD SPACER TO 1775'. PUMP 30 SX CMT. MUD SPACER TO 550'. CHECK WITH WIRELINE. FILL 5 1/2" TO SURFACE WITH 65 +/- SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: NONE  
Date/Time Plugging Completed: 01/29/2004 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 300# HULLS & 25 SX CMT. MUD SPACER BETWEEN PLUGS. 1ST PLUG AT 1775' WITH 30 SX CMT. 2ND PLUG AT 550' WITH 65 SX CMT TO SURFACE. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG. TOOK 0 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6234	6244		
6120	6132		

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 10 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
JAN 30 2004  
KCC Dodge City

Signed

Jim Holland (TECHNICIAN)

INVOICED  
DATE 2-11-04  
INV. NO. 2004061165

Form CS-2/3