

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21423-00-00
Spot: NESWSW Sec/Twnshp/Rge: 20-34S-40W
1250 feet from S Section Line, 4030 feet from E Section Line
Lease Name: MILLER M Well #: 2
County: MORTON Total Vertical Depth: 2765 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

PROD Size: 5.5 feet: 2719 WITH 365 SX CMT
RBP Size: feet: 2047
SURF Size: 8.625 feet: 516 WITH 200 SX CMT

\$89.86

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/03/2004 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PLUG AT CUT-OFF WITH 30 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2004 2:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2698'. CASING LEAK @ 1200' +/- . TOF @ 255'. TOP OF FISH LEFT IN HOLE AT 2169'. RBP @ 2047'. NO CMT ON TOP. SHOOT CASING OFF AT 810' & PUMPED 40 BBL MUD. HOLE WOULDN'T LOAD. PUMPED 200# HULLS & 30 SX CMT. DISPLACE WITH MUD. NO CIRCULATION. PULL OUT OF HOLE TO 530'. CIRCULATE HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2560	2564		
2532	2536		
2504	2508		
2476	2480		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 10 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 810' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 2-11-04
INV. NO. 2004061165

Form CP-2/3