

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20111-00-00
Spot: SESESENW Sec/Twnshp/Rge: 32-27S-34W
2540 feet from N Section Line, 2340 feet from W Section Line
Lease Name: STANLEY A Well #: 2
County: HASKELL Total Vertical Depth: 3185 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

CIBP Size: feet: 2860
PROD Size: 4.5 feet: 3184 WITH 225 SX CMT
SURF Size: 8.625 feet: 834 WITH 400 SX CMT

4103⁵¹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/23/2004 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2860'. PLUG AT 850' WITH 100 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2004 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 2860'. FL @ 460'. PUMPED 20 BBL MUD DOWN 4 1/2". COULD NOT PRESSURE CASING. SHOOT 4 1/2" OFF AT 850'. PUMP 300# HULLS & CIRCULATE HOLE WITH MUD. PUMP 100 SX CMT @ 850'. GOOD CIRCULATION. FLUID FELL IN HOLE. PULL OUT OF HOLE TO 500'. SDON. 01/26/04: COULD NOT GET DOWN WITH WIRELINE TO TAG CMT TOP. RAN BACK IN HOLE WITH 4 1/2" CASING TO 830'. FLUID LEVEL AT 400' +/- . LOAD HOLE. PUMP 50 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2957	2968		
2928	2935		
2907	2925		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 10 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 850' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
FEB - 2 2004
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED

DATE 2-11-04
INV. NO. 2004061165

Form *CSG*