

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

FEB 09 2004

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Diversified Operating Corp

Address: 15000 West 6th Ave. Suite 102 Golden, CO 80401

Phone: (303) 384-9611 Operator License #: 33060

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Scott Alberg (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. 6730
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 025-21255-00-00

Lease Name: Thomas

Well Number: 20-7-1

Spot Location (QQQQ): _____ - _____ - SW - NE
1980 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 20 Twp. 32 S. R. 22 East West

County: Clark

Date Well Completed: 1-15-04

Plugging Commenced: 1-16-04

Plugging Completed: 1-16-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
surface beds	Cond	0	80'	20'	80	0
Prod Surf		0	840' 833	8 5/8"	840' 833	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole full of 9.2 ppg drilling mud. Drill pipe and Drill collars layed down, Ran back into 860' w/ open ended drill pipe.
Set 1st plug @ 860', 50 sks, 2nd plug @ 400', 40 sks, 3rd plug @ 40', 10sks, 10 sks in mouse hole, 15 sks in rat hole. All cement: 60/40 Pozmix w/ 6% gel.

Name of Plugging Contractor: Allied Cementing Val Energy, Inc. License #: 5832

Address: PO Box 31 Russel, KS 67665 PO Box 116, Wichita, KS

Name of Party Responsible for Plugging Fees: Diversified Operating Corp

State of Colorado County, Jefferson, ss.


Terry J. Cammon (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) 15000 West 6th Ave. Suite 102 Golden, CO 80401

SUBSCRIBED and SWORN TO before me this 2nd day of February, 2004

[Signature] My Commission Expires: 4/19/2006
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202