

WELL PLUGGING RECORD

K.A.R.-82-3-117

15-159-21528-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED

FEB 11 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 15-159-21528-00-00

LEASE NAME M Pallister

WELL NUMBER 3-12

330 ft. from S Section Line

3960 ft. from E Section Line

SEC. 12 TWP. 21 RGE. 7 (E) or (W)

COUNTY Rice

Date Well Completed 1-15-1983

Plugging Commenced 1/22/04

Plugging Completed 1/26/04

LEASE OPERATOR Bruce Oil Co.

ADDRESS 1704 Limestone Rd., McPherson, KSS 67460

PHONE # (620) 241-2938 OPERATORS LICENSE NO. 5610

Character of well oil

(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 1/22/04 (date)

by Doug Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? yes not available to us

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3450

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surf Prod			205	8 5/8	205	none
			3400	5 1/2	3400	2430

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand at 3350, bail 5 sacks cement. Rip pipe at 2430, work free. Pull to 1050, pump 35 saacks cement. Pull to 600, pump 35 sacks cement. Pull to 255 and circulate with 110 sacks cement. Layed rest of pipe down,

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bruce Oil Co.


STATE OF KANSAS COUNTY OF McPHERSON, ss.

LONNY BRUCE (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Lonny Bruce
(Address) McPHERSON, KANSAS

SUBSCRIBED AND SWORN TO before me 10th day of February, 2004

My commission Expires: 12-13-05



Form CP-4 Revised 05-88

REPLACEMENT CARD

GULFCO PRODUCTION, INC.
1900 W. LOOP SO., #1900
HOUSTON, TX 77027


#3-12 M. PALLISTER

12-21-7W
C S/2 SW

CONTR STERLING DRILLING CO. CTY RICE

GEOL _____ FIELD WHERRY

ELV NA SPD 12/14/82 CARD ISSUED 6/9/83 IP P 12 B0 & 90 BW & 15 MCFGPD
MISS OH 3400-3450



SMP	Tops	Depth/Datum
HEEB	2715-1090
BR LM	2860-1235
LKC	2900-1275
CONG CHAT	3350-1725
MISS CHAT	3400-1775
RTD	3450-1825

API 15-159-21,528

8 5/8 " 205 / 200SX, 5 1/2 " 3400 / 75SX
MICT - CO, (MISS OH 3400-3450), SWB DWN, SO, NAT, SET 2
3/8 " TBG AT 3380', POP, P 12 B0 & 90 BWPD & 15 MCFGPD,
(GR 36°), 2/2/83

INFO RELEASED: 6/7/84 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS