

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE**

Form ACO-1
September 1999
Form Must Be Typed

ORIGINAL

Operator: License # 30128
Name: KENNETH S. WHITE
Address: 2400 N. Woodlawn, #115
City/State/Zip: Wichita KS 67220
Purchaser: _____
Operator Contact Person: Kenneth S. White
Phone: (316) 682-6300
Contractor: Name: Murfin Drilling Co., Inc.
License: 30606
Wellsite Geologist: Tim Hellman

RECEIVED

FEB 24 2004

KCC WICHITA

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>01/08/04</u>	<u>01/18/04</u>	<u>01/19/04</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 187-21025-0000
County: Stanton
SW NV. NE Sec. 26 Twp. 29S S. R. 41 East West
880 feet from S / N (circle one) Line of Section
2040 feet from E W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Black Stone "A" Well #: 1
Field Name: Arroyo
Producing Formation: _____
Elevation: Ground: 3337 Kelly Bushing: 3347
Total Depth: 5600 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 1663 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.


Drilling Fluid Management Plan *(Data must be collected from the Reserve Pit)*
Chloride content 800 ppm Fluid volume 1800 bbls
Dewatering method used Evaporation
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

See 1st part of 3-B-04

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Kenneth S. White
Title: Operator Date: 2/23/04
Subscribed and sworn to before me this 23rd day of February,
2004.
Notary Public: Susan M. Way
Date Commission Expires: _____



KCC Office Use ONLY

Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

ORIGINAL

Attached to and Made a Part of
ACO-1 Form for
KENNETH S. WHITE
#1 BLACK STONE "A"
880' FNL and 2040' FEL
Sec 26-29S-41W
Stanton County, Kansas
API# 15-187-21025-0000

RECEIVED

FEB 24 2004

KCC WICHITA

DST #1 5485 – 5525 (St. Louis)

30" – 30" – 30" – 30"

1st Open: Weak ¼" blow died in 25 min

2nd Open: No blow, flush tool, surged and died

Rec: 5' Drilling Mud

IFP: 18# - 20# ISIP: 20# IHP: 2744#

FFP: 16# - 24# FSIP: 24# FHP 2601#

ALLIED CEMENTING CO., INC.

13564 ORIGINAL

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley

DATE <u>1-10-04</u>	SEC. <u>26</u>	TWP. <u>29s</u>	RANGE <u>41w</u>	CALLED OUT <u>Bulk Trks 7:30 AM</u>	ON LOCATION <u>Pump Trk 3:00 PM</u>	JOB START <u>11:45 AM</u>	JOB FINISH <u>12:30 PM</u>
LEASE <u>Black Stone</u>	WELL# <u>1</u>	LOCATION <u>Johnson 4.5 1/2 W S + E JV</u>			COUNTY <u>97th Twp</u>	STATE <u>KS</u>	

OLD OR NEW (Circle one)

CONTRACTOR Murfin Drilling Rig 14

TYPE OF JOB Surface

HOLE SIZE 12 1/4 T.D. 1662'

CASING SIZE 8 7/8 DEPTH 1662.62

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 8009 MINIMUM _____

MEAS. LINE _____ SHOE JOINT 43.48'

CEMENT LEFT IN CSG. 43.48

PERFS. _____

DISPLACEMENT 103 1/4 Bbls

OWNER Same

CEMENT AMOUNT ORDERED

470 sks Lite 3 9/16 CC 1/4" F10 Seal

150 sks Com 3 9/16

COMMON	<u>150 sks</u>	@ <u>8.35</u>	<u>1252.50</u>
POZMIX		@	
GEL		@	
CHLORIDE	<u>20 sks</u>	@ <u>30.00</u>	<u>600.00</u>
Lite	<u>470 sks</u>	@ <u>7.35</u>	<u>3454.50</u>
		@	
F10 Seal	<u>1187</u>	@ <u>1.40</u>	<u>165.20</u>
		@	
		@	
HANDLING	<u>620 sks</u>	@ <u>1.15</u>	<u>713.00</u>
MILEAGE	<u>54/sk/mile</u>		<u>1550.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Dean

373-281 HELPER Andrew

BULK TRUCK

361 DRIVER Fuzzy

BULK TRUCK

218 DRIVER Lonnie

RECEIVED

TOTAL 7735.20

FEB 24 2004

REMARKS:

SERVICE
KCC WICHITA

Circulated 15 Bbls Cement To Pt ✓

Float Landed 8009

Float Held

Thank you

DEPTH OF JOB 1662'

PUMP TRUCK CHARGE _____ 1130.00

EXTRA FOOTAGE @ _____

MILEAGE 50 miles @ 3.50 175.00

PLUG 8 7/8 Rubber @ _____ 100.00

@ _____

@ _____

TOTAL 1405.00

CHARGE TO: Kenneth S. White

STREET _____

CITY _____ STATE _____ ZIP _____

8 7/8 FLOAT EQUIPMENT

Guide Shoe	@	<u>215.00</u>
AFW Insert	@	<u>325.00</u>
3-Centralizers	@ <u>55.00</u>	<u>165.00</u>
1-Basket	@	<u>180.00</u>
	@	

TOTAL 885.00

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE 10025.20

DISCOUNT 1002.52 IF PAID IN 30 DAYS

9022.68

SIGNATURE James A. [Signature]

PRINTED NAME _____

ALLIED CEMENTING CO., INC.

13567
ORIGINAL

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: oakley

DATE <u>1-19-04</u>	SEC <u>26</u>	TWP <u>28g</u>	RANGE <u>41w</u>	CALLED OUT	ON LOCATION <u>2:00 PM</u>	JOB START <u>2:40 PM</u>	JOB FINISH <u>6:00 AM</u>
LEASE <u>Block Stone 4A</u>	WELL # <u>1</u>	LOCATION <u>Johnson 45 1/2 W S/S</u>			COUNTY <u>Sedgwick</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)							

CONTRACTOR <u>Muffin Drig Rig 14</u>	OWNER <u>same</u>
TYPE OF JOB <u>PTA</u>	
HOLE SIZE <u>7 7/8</u>	T.D. <u>5600'</u>
CASING SIZE	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH <u>2460'</u>
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	
EQUIPMENT	
PUMP TRUCK CEMENTER <u>Dean</u>	
# <u>373-281</u> HELPER <u>Andrew</u>	
BULK TRUCK	
# <u>218</u> DRIVER <u>Mike</u>	
BULK TRUCK	
#	DRIVER

CEMENT AMOUNT ORDERED	<u>225 SKS 60/40 670 Gel 1/4" Plug Seal</u>	
COMMON	<u>135 SKS @ 8.35</u>	<u>1127.25</u>
POZMIX	<u>90 SKS @ 3.80</u>	<u>342.00</u>
GEL	<u>12 SKS @ 10.00</u>	<u>120.00</u>
CHLORIDE	@	
	@	<u>78.40</u>
<u>P/O Seal 567</u>	<u>@ 1.40</u>	<u>784.00</u>
	@	
	@	<u>258.75</u>
HANDLING <u>225 SKS</u>	<u>@ 1.15</u>	<u>258.75</u>
MILEAGE <u>54 SK/mile</u>		<u>562.50</u>

RECEIVED

TOTAL ~~5523.00~~
2488.90

REMARKS:

1st Plug 2460' w/ 100 SKS
2nd Plug 1690' w/ 50 SKS
3rd Plug 600' w/ 40 SKS
4th Plug 401' w/ 10 SKS
15 SKS in Rat Hole
10 SKS in mouse Hole
Thank you

KCC WICHITA

SERVICE

DEPTH OF JOB	<u>2460'</u>	
PUMP TRUCK CHARGE		<u>130.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>50 Miles</u>	<u>@ 3.50</u>	<u>175.00</u>
PLUG <u>8 7/8 Dry Hole</u>	@	<u>23.00</u>
	@	
	@	

TOTAL 828.00

CHARGE TO: Kenneth S. White

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME _____