

ORIGINAL

Operator Name: Pelican Hill Oil & Gas, Inc Lease Name: Okeson Well #: 3-8

Sec. 8 Twp. 15 S. R. 41 East West County: Wallace

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

<p>Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i></p> <p>Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i></p> <p>List All E. Logs Run: Sonic Dual Induction</p>	<p><input checked="" type="checkbox"/> Log <input type="checkbox"/> Sample</p> <p>Formation (Top), Depth and Datum</p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Name</th> <th>Top</th> <th>Datum</th> </tr> </thead> <tbody> <tr> <td>Morrow Shale</td> <td>4941</td> <td>-1167</td> </tr> <tr> <td>Morrow Sand Upper</td> <td>4962</td> <td>-1190</td> </tr> <tr> <td>Morrow Lime</td> <td>5046</td> <td>-1273</td> </tr> </tbody> </table>	Name	Top	Datum	Morrow Shale	4941	-1167	Morrow Sand Upper	4962	-1190	Morrow Lime	5046	-1273
Name	Top	Datum											
Morrow Shale	4941	-1167											
Morrow Sand Upper	4962	-1190											
Morrow Lime	5046	-1273											

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Production SURF →	12-1/4"	8-5/8"	24.00	380'	Common	365	
	7-7/8"	5-1/2"	15.50	5127'	Common	150	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4969' - 4972'	TCP Charges 12 total	
	RECEIVED KANSAS CORPORATION COMMISSION		
	FEB 16 2004		
	CONSERVATION DIVISION WICHITA, KS		

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2-7/8"	5022'		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

Date of First, Resumerd Production, SWD or Enhr. 11-15-03	Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
--	---	--	--	--

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	20	Not Oper.	0		

Disposition of Gas Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____

ALLIED CEMENTING CO., INC. 14256 ORIGINAL

P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley

DATE <u>10-21-03</u>	SEC. <u>8</u>	TWP. <u>15^s</u>	RANGE <u>41^w</u>	CALLED OUT	ON LOCATION <u>1:00Am</u>	JOB START <u>7:30 Am</u>	JOB FINISH <u>8:30 Am</u>
LEASE <u>Okeson</u>	WELL # <u>3-8</u>	LOCATION <u>Sharon Springs 9W-8S</u>			COUNTY <u>Wallace</u>	STATE <u>Kan</u>	
OLD OR <u>NEW</u> (Circle one)				<u>NE-145</u>			

CONTRACTOR Mur Fin Drls Co #14

TYPE OF JOB Production

HOLE SIZE 7 7/8" T.D. 5128'

CASING SIZE 5 1/2" DEPTH 5127'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL Port Collar DEPTH 2768'

PRES. MAX 1500# MINIMUM _____

MEAS. LINE _____ SHOE JOINT 21.10'

CEMENT LEFT IN CSG. 21.10'

PERFS. _____

DISPLACEMENT 123-BRL

OWNER Same

CEMENT

AMOUNT ORDERED 150 SKS ASC, 1/2# Flo-Seal

500 gal WFR-2, 2-Gal Cla-Pro

<u>ASC</u>	<u>150 SKS</u>	@ <u>9⁰⁰</u>	<u>1,350⁰⁰</u>
POZMIX		@	
GEL		@	
CHLORIDE		@	
<u>WFR-2</u>	<u>500 gal</u>	@ <u>1⁰⁰</u>	<u>500⁰⁰</u>
<u>Cl-a-Pro</u>	<u>2-gal</u>	@ <u>22⁹⁰</u>	<u>45⁸⁰</u>
<u>Flo-Seal</u>	<u>38#</u>	@ <u>1⁴⁰</u>	<u>53²⁰</u>
HANDLING	<u>150 SKS</u>	@ <u>1¹⁵</u>	<u>172⁵⁰</u>
LEASE	<u>54 per sk/mile</u>		<u>510⁰⁰</u>

EQUIPMENT

PUMP TRUCK CEMENTER Walt

191 HELPER Wayne

BULK TRUCK

218 DRIVER Larry

BULK TRUCK

_____ DRIVER _____

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 02 2004

TOTAL 2,631⁵⁰

REMARKS:

CONSERVATION DIVISION
WICHITA, KS

SERVICE

Mixed 10 SKS in M.H.

Mixed 15 SKS in R.H.

Pumped 500 gal WFR-2

Mixed 125 SKS ASC

Clear Pump + Lines Displaced 123 1/2

2 900# Landed Plus 2 1500#

Last Pressure to 200# Shut in

[Signature]

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>1,130⁰⁰</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>68 miles</u>	@ <u>3⁵⁰</u>	<u>238⁰⁰</u>
PLUG	<u>5 1/2 Rubber</u>	@	<u>60⁰⁰</u>
		@	
		@	

TOTAL 1,428⁰⁰

CHARGE TO: Pelican Hill

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	<u>5 1/2</u>		
1- Guide Shoe		@	<u>150⁰⁰</u>
1- AFU Insert		@	<u>235⁰⁰</u>
10- Centralizers		@ <u>50⁰⁰</u>	<u>500⁰⁰</u>
1- Basket		@	<u>128⁰⁰</u>
1- Port Collar		@	<u>1,750⁰⁰</u>

TOTAL 2,763⁰⁰

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME _____

ALLIED CEMENTING CO., INC. 14850 ORIGINAL

.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley

<u>10-11-0</u>	SEC. <u>8</u>	TWP. <u>15s</u>	RANGE <u>41w</u>	CALLED OUT	ON LOCATION <u>10:00 PM</u>	JOB START <u>5:00 AM</u>	JOB FINISH <u>5:15 AM</u>
LEASE <u>OKason</u>		WELL # <u>3-8</u>		LOCATION <u>Sharon Springs</u>		COUNTY <u>Wallace</u>	STATE <u>KS</u>

OLD OR NEW (Circle one)

CONTRACTOR Murfin Drtg Rig 14 OWNER Same

TYPE OF JOB Surface

HOLE SIZE <u>12 1/4</u>	T.D. <u>380'</u>	CEMENT ordered used 80 SKS AMOUNT ORDERED <u>100 SK COM 390 CU TO 1"</u> <u>285 SKS COM 390 CU 290 GEL</u> <u>(1/4" PLO Seal furnish by Rig)</u>
CASING SIZE <u>8 5/8</u>	DEPTH <u>380'</u>	
TUBING SIZE	DEPTH	
DRILL PIPE	DEPTH	
TOOL	DEPTH	
PRES. MAX <u>400#</u>	MINIMUM	COMMON <u>365 SKS @ 8.35</u> <u>3047.75</u>
MEAS. LINE	SHOE JOINT <u>45.75'</u>	POZMIX @
CEMENT LEFT IN CSG. <u>45.75'</u>		GEL <u>5 SKS @ 10.00</u> <u>50.00</u>
PERFS.		CHLORIDE <u>13 SKS @ 30.00</u> <u>390.00</u>
DISPLACEMENT <u>2 1/4</u>		@
EQUIPMENT		@
PUMP TRUCK CEMENTER <u>Dean</u>		@
# <u>373-281</u> HELPER <u>Andrew</u>		@
BULK TRUCK		@
# <u>218</u> DRIVER <u>Larry</u>	RECEIVED MILEAGE <u>59 / SK / MI</u>	HANDLING <u>385 SKS @ 1.15</u> <u>442.75</u>
BULK TRUCK	KANSAS CORPORATION COMMISSION	<u>1309.00</u>
#	DRIVER	TOTAL <u>5239.50</u>

CONSERVATION DIVISION
WICHITA, KS

REMARKS: Cement did not circulate
Plug landed on Baffle Plate
1" w/ 80 SKS cement to surface
Thank you

DEPTH OF JOB <u>380'</u>	
PUMP TRUCK CHARGE <u>520.00</u>	
EXTRA FOOTAGE @	
MILEAGE <u>68 miles @ 3.50</u> <u>238.00</u>	
PLUG <u>8 5/8 Surface @</u> <u>45.00</u>	
@	
@	
TOTAL <u>803.00</u>	

CHARGE TO: Pelican Hill Oil & Gas Inc

STREET _____

CITY _____ STATE _____ ZIP _____

9/5/6

FLOAT EQUIPMENT

<u>Baffle Plate @</u> <u>45.00</u>
<u>1 Centralizer @</u> <u>55.00</u>
@
@
@
TOTAL <u>100.00</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Alvin Blumberg

PRINTED NAME _____