

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1974
CONSERVATION DIVISION
Wichita, Kansas

15-147-20173-00-00

Operator's Full Name Phillips Oil Operating Co.

Complete Address Box 706 Enid, Okla. 73701

Lease Name Parker "A" Well No. 1

Location NW NW NW Sec. 27 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3485'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 7:30 A Day 22 Month 6 Year 1974

The above well was plugged as follows:

RTD 3485' 8 5/8 csg set at 233' cwc Cmt. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 1050' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Mussey
Well Plugging Supervisor

INVOICED

DATE 6/24/74

INV. NO. 9383-W