

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
Rev. 6-26-62
RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-00410-00-00 14 20

Operator's Full Name Red Barron Production

Complete Address: Box 55 Phillipsburg, Kansas

Lease Name Parker Well No. 1

Location C SW NW Sec. 27 Twp. 1 Rge. 18 (E) (W) X

County Phillips Total Depth 3610'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 5 P Day 14 Month 6 Year 1968

The Above well was plugged as follows:

Total Depth 3610' 8 5/8 csg set at 193' cwc 130 sc.

4 1/2 csg set at 3604' cw 150 sc cement.

4 1/2 csg PBTD 3490' and perf. 3414-18.

Filled 4 1/2 csg with sand to 3400' and dumped 4 sc cement with dump bailer.

Recov. 1420' of 5 1/2 csg.

Pumped thru 8 5/8 plg container with 35 sc gel and 130 sc cement.

Cem. (0-30) gel (30-165) cem. (165-225) gel (225-850) cem. (850-1170) gel(1170-TD).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/17/68

INV. NO. 4952-11

Signed: Leo F. Massey
Well Plugging Supervisor