

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

05-17-76
MAY 17 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

15-147-20007-00-00

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - - (of this well)

Operator's Full Name Petroleum Management, Inc.

Complete Address 400 North Woodlawn, Suite 201, Wichita, Kansas 67208

Lease Name Rakestraw Well No. 2

Location W/2 NE NE Sec. 31 Twp. 1 Rge. (E) (W) 18

County Phillips Total Depth 3670'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 12:15 P Day 15 Month 5 Year 1976

The above well was plugged as follows:

Total Depth 3670' 8 5/8 csg set 204' cwc 150 sk.

4 1/2 csg set 3669' cw 200 sk cem.

4 1/2 csg PBSD 3637' with PFS (3444'-48') & (3587'-3591')

Set 4 1/2" wood plug at 3400' -poured 10' sand -dumped 3 sk cem W/dump bailer.

Cutoff & recovered 1205' of 4 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water with

300 lbs hulls -70 sk 50-50 poz 6% -15 sk gel & water -released 8 5/8 plug & 50 sk

50-50 poz 6% & shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 5/17/76

INV. NO. 3221-W