

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-147-30170-00-00

FILE NO. _____

LOCATION NE NE NE

SEC. 27 TWP. 1 RGE. 18

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Babcock

Operator B & R Drg Co Address Russell, Kans

Field _____ County Phillips

Total Depth 3800 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 185' circulated with cement - 5 1/2" at 3522' with
100 sax behind.

Lane-wells plugs to 3402', top perforation at 3395',
filledw with chat to 3390', run 4 sax cement with dump bailer,
mud to 180', set wood plug and 15 sax cement, mud to 35'
set rock bridge and 10 sax cement to bottom cellar.

RECEIVED

Conservation-Div.
JUN 26 1950

STATE CORPORATION
COMMISSION

Edgar
District Conservation Agent

Date 6-20-50

PLUGGING
FILE SEC 27 T 1 R 18
BOOK PAGE 12 LINE 4