

DISTRICT CONSERVATION AGENT'S REPORT

*[Handwritten signature]*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-147-30187-00 00

FILE NO. \_\_\_\_\_

LOCATION NW NE NW

SEC. 27 TWP. 1 RGE. 18

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease B abcock

Operator B & R Drg. ~~CO~~ INC. Address Russell, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3439 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 176' circulated with cement - 5 1/2" at 3439' with  
150' sax behind - drilled out to 3436', top perf 3293'.

Filled with sand to 3280' set 4 sax cement with dump bailer  
pulled 2810' 5 1/2", filled with mud to 175' set rock and 15  
sax cement, filled with mud to 35', set rock and 10 sax  
cement to bottom cellar.

RECD  
STATE CORP.

JUN 16 1951

CONSERVATION

*[Handwritten signature]*

District Conservation Agent

Date 6-12-51

PLUGGING 182  
FILE SEC 27 T 18 R 18  
BOOK PAGE 88 LINE 27