

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -147 20,016-00-00 (of this well)

Operator's Full Name DON H PEAKER

Complete Address P.O. BOX 1595 PUEBLO, COLORADO. 81002

Lease Name O'NEILL Well No. #1

Location NW-NW-NW Sec. 22 Twp. 1 Rge. 18 (E) (W) W

County PHILLIPS Total Depth 3585 FE

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated _____

Plugging Contractor MELSO CASING PULLING

Address BOX 176 CHASE, MANA, 67524 License No. _____

Operation Completed: Hour 2:45 Day 6 Month AUG. Year 1980

The Above well was plugged as follows:

8 5/8" 208 FT SP. CUL -> 4 1/2" SET AT 3584 FT w/ 200 FT CMT.

OPEN HOLE - SAND BOTTOM TO 3500 FT AND w/ 1/4" SET CMT.

SHOT PIPE 4 TIMES - RECOVERED 1428 FT

ORDERED 140 FT 50/50 POZ MIX 6% GEL - 18 FT GEL - 5 FT HULL'S

AND 8 5/8" PLUG. -> PUMPED IN WITH PUMP TOUCH.

PUT IN 3 FT HULL'S - 8 FT GEL. -> 70 FT CMT. -> 10 FT GEL

2 FT HULL'S -> RELEASED PLUG. AND 70 FT CMT.

MAX PRESSURE - 0 CEMENTED BY ALLIED CMT.

RECEIVED
STATE CORPORATION COMMISSION
AUG - 08 - 80
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-8-80

INV. NO. 2799-W

Signed: Marvin Schmidt
Well Plugging Supervisor