

15-147-00564-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Petroleum Management, Inc.  
Complete Address 400 North Woodlawn, Suite 201, Wichita, Kansas 67208  
Lease Name Rakestraw Well No. 1  
Location SW SW NE Sec. 31 Twp. 1 Rge. (E) (W) 18  
County Phillips Total Depth 3535'  
Abandoned Oil Well XX Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated   
Plugging Contractor Southwest Casing Pulling  
Address Box 364, Great Bend, Kansas 67530 License No. 399  
Operation Completed: Hour 10:15 A Day 15 Month 5 Year 1976

The above well was plugged as follows:  
Total Depth 3535' 8 5/8 csg set 188' cwc 140 sk.  
5 1/2 csg set 3533' cw 150 sk cem.  
5 1/2 csg PFS (3441'-3447') & (3518'-3522')  
Set 5 1/2 wood plug at 3400' - poured 10' sand - dumped 4 sk cem W/dump bailer.  
Cutoff & recovered 1310' of 5 1/2 csg.  
Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water  
W/300 lbs hulls -70 sk 50-50 poz 6% -15 sk gel & water -released 8 5/8 plug &  
50 sk 50-50 poz 6% & shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 5/17/76  
INV. NO. 3218-W