

4-041812

15-147-00422-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 11-28-50

10-24

NE NW SW /4 SEC. 31, 01 S, 18 W
2310 feet from N section line
990 feet from W section line

Operator license# 5242

Lease: Huffstutter Well # C-2

Operator: Petroleum Management, Inc.

County: Phillips 115.31

Address: 14201 East Central
Wichita, Kansas 67230

Well total depth 3548 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 188 feet
w/125sx.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 24 Month: October Year 1996

Plugging proposal received from: Gary Reed

Company: Petroleum Management, Inc. Phone:

Were: Order 250 sxs 60/40 pozmix with 10% gel with 1/4# F.C. - 500# hulls.
5 1/2" casing set at 3548' w/150 sxs cement. Perf. at 3443' - 3538'. Anhy. at 1850' -
Dakota at 1010' - W.L.M. at 3450'.

RECEIVED
KANSAS
NOV 15 1996
11-6-96
Rec

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:30 P.M., Day: 24, Month: October, Year: 1996

Actual plugging report: R.U. Cementers to 8 5/8" S.P. with 25 sxs cement plus 100# hulls.
Max. P.S.I. 300#. R.U. Cementers to 5 1/2" casing. Squeezed 40 sxs cement with 400# hulls
followed with 14 sxs gel, followed with 175 sxs cement. Max. P.S.I. 400#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

INVOICED

DATE NOV 07 1996
INV. NO. 46934

Dennis L. Hamel
(agent)