

4-041572

4-26

15-147-00424-00-00

API number: 15- - 10-19-50

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NW /4 SEC. 31, 01 S, 18 W
2310 feet from N section line
990 feet from W section line

Operator license# 5242

Lease W.A. Jackson well # 3

Operator: Petroleum Management, Inc.

County Phillips

Address: 1420 East Central
Wichita, Kansas 67230

Well total depth 3530 feet ^{114.72}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 245 feet
w/165 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 26 Month: April Year: 94

Plugging proposal received from: Don Keener

Company: Petroleum Management, Inc. Phone:

Were: 5 1/2" casing set @ 3530' w/150 sxs. cement. Perf. @ 3500' -
3520'. Anhy. @ 1720' - Dakota @ 1260' - Remove B.P. @ 3200'.
Ordered 200 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls
and 7 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:30P.M., Day: 26, Month: April, Year: 94

Actual plugging report: Spot cement through tubing from 3500'. 25 sxs.
with 200# hulls followed with 7 sxs. gel followed with 85 sxs. cement
with 200# hulls. Pulled tubing and squeezed additional 35 sxs. cement
at surface. Max. 400 P.S.I. Hooked-up to 8 5/8" squeezed 50 sxs.
cement with 100# hulls. Max. 200# P.S.I.

RECEIVED
STATE CORPORATION COMMISSION

MAY 05 1994

Remarks: Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL

CONSERVATION DIVISION
Wichita, Kansas

I did [] observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE MAY 09 1994

INV. NO. 40400

4-26