


15-147-30170-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Phillips County. Sec. 27 Twp. 1S Rge. 18 (E) W (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines CN/2 NE NE  
Lease Owner B & R Drilling, Inc.  
Lease Name Babcock Well No. # 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 21, 1950 19  
Application for plugging filed June 17, 1950 Verbally 19  
Application for plugging approved June 17, 1950 Verbally 19  
Plugging commenced June 17, 1950 19  
Plugging completed June 20, 1950 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3800' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	185'	None
				5 1/2"	3522'	2923'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

Filled hole with crushed rock from 3402' to 3390'  
dumped 4 sax cement at 3390' with dump bailer. Top  
of cement 3367'. Filled with mud to 180', set rock  
bridge, dumped 15 sax cement, top of cement 130'.  
Filled with mud to 35', dumped 10 sax cement for cap.

REC  
JUN 26 1950  
STATE OF  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R DRILLING, INC.  
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Harold Wurst, Treasurer (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of June, 1950  
Notary Public.

My commission expires 2-8-54

23-3273-s 4-50-10M

PLUGGING  
FILE SEC 27 T 1 R 18 W  
BOOK PAGE 13 LINE 4

B & R Drilling, Inc.  
Babecock #1

SW/2 NE NE Sec. 27-18-18W  
Phillips County, Kansas

Total Depth: 3800'  
Comm: 5-6-50  
Comp: 5-21-50

15-147-30170-00-00

**Casing**

8 5/8" Set @ 185'  
5 1/2" Set @ 3522'

**Cement**

125 Sacks of Portland Ideal  
100 Sacks of Portland Ideal

Formation	Depth:
Surface Clay- Shale	75
Shale-Sand	135
Shale-Shells	970
Sand-Shale	1120
Shale-Shells	1340
Sand	1355
Hells-Shale	1610
Shale-RedBed	1760
Shale-Shells-RedBed	1765
Anhydrite	1790
Shale-Shells	1955
Shale-Lime	3030
Lime	3105
Shale-Lime	3190
Lime	3240
Lime-Shale	3360
Lime	3460
Lime-Shale	3505
Lime	3635
Lime-Shale	3685
Lime	3800

STATE OF KANSAS )  
                          )SS  
RUSSELL COUNTY )

I hereby certify that the above information is true  
and correct to the best of my knowledge.

*Violet Keller*  
JUN 28 1950  
COMMISSION  
KANSAS

Subscribed and sworn to before me this 7th day of June, 1950

*Dean Robert*  
Notary Public

My commission expires: 2-8-54

PLUGGING  
FILE SEC 27 T 1 R 18W  
BOOK PAGE 13 LINE 4