


15-147-00650-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Phillips County. Sec. 31 Twp. 1S Rge. 18 (E) W(W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SE NW  
Lease Owner Laura Jane Oil Company  
Lease Name Jackson Well No. 4  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 11-15-50 19  
Application for plugging filed 6-17-52 19  
Application for plugging approved 6-17-52 19  
Plugging commenced 6-13-52 19  
Plugging completed 6-15-52 19  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3515 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				4-1/2"	3509'	1281'
				8-5/8"	170'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 170', set 10' rock bridge to 160' and ran 15 sacks of cement. Mudded hole to 40', set 10' rock bridge and ran 10 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Laura Jane Oil Company  
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. ...  
817 Central Building  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of June, 1956  
My commission expires February 8, 1956

Gorgia D. Mills  
Notary Public.

23-3273-s 4-50-10M  
PLUGGING  
FILE SEC 31 T 1 R 1  
BOOK PAGE 24 LINE 2  
JUN 25 1952  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

15-147-00650-00-00

DRILLING LOG

WELL NAME: Jackson #4  
OWNERS: Laura Jane Oil Co.  
CONTRACTORS: Laura Jane Oil Co.  
COMM: 11-6-50  
COMP: 11-15-50

LOCATION: NW SE NW, <sup>31</sup>13-1S-18W  
Phillips County, Ks.  
ELEVATION: 2221 DF  
2219 GR  
PRODUCTION:  
CASING RECORD: 8 5/8" @170'  
3515' 4 1/2"

<u>FORMATION</u>	<u>TO</u>	
Soil & Clay	65	
Sand	150	
Lime	170	
Shale-Shells	1800	
Anhydrite	1880	
Shale	1965	
Shale - Lime	2860	Tops from rotary bushing
Lime	2960	
Lime- Shale	3095	Top Heebner Shale 3360
Lime	3370	Top Lansing K. C. 3387
Shale	3387	
Lime	3515	TD Rotary (Casing on bottom)

Drilled in by Cable tools.

I certify that the above is a true and correct copy of the log of the Jackson #4, NW SE NW, 31-1S-18W, Phillips County, Kansas, to the best of my knowledge.

LAURA JANE OIL CO., INC.

BY James Armour  
JAME ARMOUR

Sworn and subscribed to before me this 23rd day of June, 1952.

Georgia K Mills  
NOTARY PUBLIC

My Comm. Expires Feb. 8, 1956.

PLUGGING  
FILE NO. 31-1-1-18W  
24 2

STATE CORP. COMMISSION  
WICHITA, KANSAS  
JUNE 25, 1952