

API NUMBER 11-51

LEASE NAME Jackson "B"

WELL NUMBER 4

SPOT LOCATION SW NW SW

SEC. 28 TWP. 1S RGE. 18 XXXXX (W)

COUNTY Phillips

Date Well Completed 11-51

Plugging Commenced 8-19-85

Plugging Completed 8-19-85

15-147-00728-00-00

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Ladd Petroleum Corporation

ADDRESS Box 520 Great Bend, Kansas 67530

PHONE # (316) 792-3571 OPERATORS LICENSE NO. 6029

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays Kansas

Is ACO-1 filed? If not, is well log attached?

Producing formation LKC Depth to top 3424 bottom 3467 T.D. 3521

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil & Water			8 5/8 5 1/2	189 3518	None None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Down 5 1/2 csg mixed 40 sx cement 60/40 poz w/5 sx hulls-15 sx Gel w/5 sx Hulls-110 sx cement w/5 sx hulls, SI Press 700#
Between 5 1/2 & 8 5/8 csg mixed 75 sx cement w/5 hulls-10 sx Gel w/5 hulls-75 sx cement SI Press. 300#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No.
 Address Great Bend, Kansas 67530

STATE OF COUNTY OF , ss.


Jerry Rice

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Rice
 (Address) Box 520 Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3 day of September, 1985



My Commission expires:

RECEIVED
 STATE CORPORATION COMMISSION
 Notary Public
Ramona L. Dunlap

SEP 4 1985