

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-00734-00-00

API NUMBER 12-14-51

LEASE NAME Jackson "D"

WELL NUMBER 2

SPOT LOCATION SW SW SE

SEC. 28TWP. 1S RGE. 18 XXXXX(W)

COUNTY Phillips

Date Well Completed 12-14-51

Plugging Commenced 8-19-85

Plugging Completed 8-19-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Ladd Petroleum Corporation

ADDRESS Box 520, Great Bend, Ks. 67530

PHONE #(316) 792-3571 OPERATORS LICENSE NO. 6029

Character of Well Input
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation LKC Depth to top 3467 bottom 3451 T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil & Water	3451	3467	8 5/8 5 1/2	192 3520	None None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Down 5 1/2 csg mixed 40 sx 60/40 poz w/5 sx hulls & 15 sx gel mud w/5 sx hulls, 110 sx 60/40 poz w/5 sx hulls. SI Press. 700#
Between 5 1/2 & 8 5/8 mixed 75 sx cement w/5 sx hulls, 10 sx gel mud w/5 sx hulls, 75 sx cement 60/40 poz, SI Press. 300#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____
 Address Great Bend, Kansas 67530

STATE OF _____ COUNTY OF _____, ss.

Jerry Rice (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed that the same are true and correct, so help me God. STATE CORPORATION COMMISSION

(Signature) Jerry Rice
 (Address) Box 520, Great Bend, Ks. 67530

SEP 4 1985

SUBSCRIBED AND SWORN TO before me this 3 day of September, 1985
 Wichita, Kansas

Ramona L. Dunlap
 NOTARY PUBLIC
 State of Kansas
 MY COMMISSION EXPIRES 7-23-88

My Commission expires: _____

NATIONAL ASSOCIATED PETROLEUM CO.

Office Memorandum

15-147-00734-00-01

From John P. Deibel, Jr.

Date April 15, 1952

To Forrest H. Lindsay

Subject #2 T. W. Jackson "D", SW SW SE

Sec. 28-1S-18W, Phillips Co., Kan

Type: Huffstutter N.E. Pool Elevation: 2206' D.F.
 Status: Oil well
 Total Depth: 3532' Driller; 3533' Schlumberger
 Dates: Spud November 23, 1951; Under surface November 25, 1951;
 Long string December 4, 1952
 Casing: Ran 194' of 8-5/8" surface casing set at 194' w/125 sacks cement.
 Ran 114 jts. of 5 1/2" casing set at 3530' w/150 sacks cement.
 Special Tests: Johnston Testers; Schlumberger Electric Survey

GEOLOGIC RECORD

<u>Formation</u>	<u>Sample</u>	<u>Schlumberger</u>
Heebner shale		3360-3365
Lansing - Kansas City		3389
Zone 1		3389-94
Zone 2		3404-26
Zone 3		3438-50
Zone 4		3458-64
Zone 5		3466-80
Zone 6		3484-92
Zone 7		3496-3512

RECEIVED
 NATIONAL PETROLEUM COMMISSION

JUN 06 1952

Geological Survey
 William R. Kuylen