


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Phillips County, Sec. 29 Twp. 1 Rge. 18 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Spector Pipe and Supply Inc.
Lease Name Federal Farm Mortgage Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 8-1-50 19__
Application for plugging filed Aug. 28, 1966 19__
Application for plugging approved Aug. 29, 1966 19__
Plugging commenced September 19, 1966 19__
Plugging completed September 20, 1966 19__
Reason for abandonment of well or producing formation failure to produce
profitably
If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Kansas City Depth to top 3430 Bottom 3555 Total Depth of Well 3558 ft. feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	225 ft.	none
				5 1/2" OD	3555	1410.00

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3350 feet. Sand to 3300 feet, and dumped 5 sacks of cement. Circulated mud at 600 feet and dumped 25 sacks of cement at 540 feet. Pumped 20 sacks of cement at 225 feet and 10 sacks of cement from 30 feet to 0 feet.

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1966
SEP 28, 1966
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lynch Casing Pulling Co. 457
Address R. Rt. 4, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Spector Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 1966

My commission expires March 9, 1970 W. H. Dawson Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- FELDT-MAYTAG & CO.
Farm- Federal Farm Mortgage No. 1

SEC. 29 T. 1 R. 10N
NW NW SW

Total Depth. 3682'
Comm. 5-19-58 Comp. 5-28-58
Shot or Treated.
Contractor. Lewis Drilling Company
Issued. 12-6-58

County Phillips
KANSAS



CASING:

8 5/8" 205'
5 1/2" 3665'

15-147-00123-00-00

Elevation. 2255. KB.

Production. 10 BOPD

Figures Indicate Bottom of Formations.

surface soil and sand	60
clay and sand	206
shale	1230
shale and sand	1855
anhydrite	1880
lime and shale	2740
lime	3682
Total Depth	

GEOLOGICAL TOPS	SAMPLE	ELECTRIC LOG
Heebner	3410	3411
Toronto	3440	3439
Lansing Kansas City	3456	3455
Base Kansas City	3662	3662

DST #1 3450-72 Open 1 hr: recovered 8' of mud: BHP 600# (initial bottom hole pressure failed to record due to error in air chamber)

DST #2 3516-38 Open 1 1/2 hrs. recovered 120' gas, 256' of very muddy oil and 60' of free oil: initial BHP 1050#, Final BHP 775#, Final Flow Pressure 125#.

DST #3 3538-60 Open 1 1/2 hrs.: recovered 90' gas, 140' of very heavily oil cut mud and 10' of free oil; Initial BHP 1125#, FBHP 875#.

DST #4 3594-3616 Open 1 hr., recovered 8' of slightly oil cut mud; Initial BHP 850#; Final Pressure record 0#. (The Final bottom hole pressure appeared somewhat doubtful as to whether the recorder was in proper calibration)

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1966
CONSERVATION DIVISION
Wichita, Kansas