

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD 15-147-20340-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Phillips SEC. 29 TWP. 1S RGE. 18W E/W
 Location as in quarters or footage from lines:
C W $\frac{1}{2}$ W $\frac{1}{2}$ SW $\frac{1}{4}$

Lease Owner Baird Oil Company
 Lease Name GODDARD Well No. 1
 Office Address Box 7, Logan, Kansas 67646
 Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
 Date Well Completed July 18, 1981
 Application for plugging filed July 18, 1981
 Plugging commenced July 18, 1981
 Plugging completed July 18, 1981

Locate Well
 correctly on above
 Section Platt.

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
 Producing formation _____ Depth to top _____ bottom T.D. 3683'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 1140' with 65 sx.
Set 2nd plug @ 270' with 35 sx.
Set 3rd plug @ 40' with 5 sx.
Plug was down @ 7:00 a.m., 7/18/81.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Cntr., Wichita, KS
 (Address) 67202

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 19 81

My Commission expires: 7-13-81

Elizabeth G. Terry Notary Public.



RECEIVED
 STATE CORPORATION COMMISSION

291381 July 29, 81

CONSERVATION DIVISION
 Wichita, Kansas

CONTRACTOR'S WELL LOG

15-147-20340-00-00

OPERATOR: Baird Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: GODDARD #1
 LOCATION: C W $\frac{1}{2}$ W $\frac{1}{2}$ SW $\frac{1}{4}$, Sec. 29-1S-18W
 Phillips County, Kansas
 SPUD DATE: 7/10/81
 COMPLETION DATE: 7/18/81

0	218	Clay & Shale
218	948	Shale
948	1832	Sand & Shale
1832	1855	Anhydrite
1855	2137	Sand & Shale
2137	2881	Shale & Lime
2881	3445	Lime & Shale
3445	3500	Lime
3500	3518	Lime & Shale
3518	3683	Lime
	3683	Rotary Total Depth

Spud hole @ 5:00 p.m., 7/10/81. Drilled 218' of a 12 $\frac{1}{4}$ " hole. Ran 5 joints of 8 5/8" 20# casing set @ 217'. Cemented with 155 sx. of Class A, 2% Gel, 3% c.c. Cement did circulate. Plug was down @ 11:00 p.m., 7/10/81.

3638' TD. Set 1st plug @ 1140' with 65 sx. Set 2nd plug @ 270' with 35 sx. Set 3rd plug @ 40' Solid Bridge with 5 sx. in Rathole, 50-50 posmix, 4% gel, 3% c.c. Plug was down @ 7:00 a.m., 7/18/81.

SAMPLE TOPS:

Anhydrite 1832' - 1855'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the GODDARD #1, C W $\frac{1}{2}$ W $\frac{1}{2}$ SW $\frac{1}{4}$, Section 29-1S-18W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 23rd day of July, 1981.

Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my commission expires 7-13-85

RECEIVED
 STATE CORPORATION COMMISSION

III 29 July 29, 1981

CONSERVATION DIVISION
 Wichita, Kansas

