

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00411-00-00

API NUMBER NA

LEASE NAME Bennett A

WELL NUMBER one

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

S¹/₂SW¹/₄SE¹/₄ Ft. from S Section Line
Ft. from E Section Line

SEC. 29 TWP. 1S RGE. 18 (X) or (W)

COUNTY Phillips

Date Well Completed 5-24-60

Plugging Commenced 9-30-85

Plugging Completed 9-30-85

LEASE OPERATOR One Way Inc

ADDRESS P.O. Box 336 Wray, Co. 80758

PHONE# (303) 332-4743 OPERATORS LICENSE NO. 9597

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #6 1014 Cody Hays KS 67601

Is ACO-1 filed? No If not, is well log attached? Previously submitted with app.

Producing Formation Tancing Ks City Depth to Top 3454 Bottom 3628 T.D. 3690

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Tancing KC</u>	<u>Oil</u>	<u>3484</u>	<u>584</u>	<u>4 1/2</u>	<u>3690</u>	<u>-0-</u>
<u>Dakota</u>	<u>Water</u>	<u>500</u>	<u>680</u>	<u>4 1/2</u>	<u>3690</u>	<u>-0-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Down 4 1/2" csg at 800# max pressure. Mixed 50 sks cement, 50 sks cement with 250# hulls, 13 sks gel with 250# hulls, 100 sks cement with 250# hulls and shut in. Down annulns, (8 5/8" csg.). Mixed 7 sks gel with 250# hulls, 150 sks cement and shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor One Way Inc. License No. 9597

Address P.O. Box 336 Wray, Co. 80758

STATE OF Colo. COUNTY OF Yuma, ss.

George H. Peaker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
George H. Peaker President

(Address) P.O. Box 336 Wray, Co. 80758

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 85

[Signature]
Notary Public

My Commission Expires: 7-18-88

RECEIVED
STATE CORPORATION COMMISSION
3636 2nd Wray, CO 80758

OCT 23 1985
10-23-1985
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84