


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-147-00414-00-00 Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Phillip County, Sec. 29 Twp. 1 Rge. 18 (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Spector Pipe and Supply Inc.
Lease Name Fisher Well No. 2
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 2-28-60 19
Application for plugging filed Aug. 28, 1966 19
Application for plugging approved Aug. 29, 1966 19
Plugging commenced September 17, 1966 19
Plugging completed September 18, 1966 19
Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Kansas City Depth to top 3401 Bottom 3611 Total Depth of Well 3630 feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	227 ft.	none
				4 1/2" OD	3632 ft.	1152.74

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 3350 feet. Sand to 3300 feet and dumped 4 sacks of cement. Circulated mud at 600 feet and dumped 25 sacks of cement at 540 feet. Pumped 20 sacks of cement at 225 feet and put 10 sacks on top.

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lynch Casing Pulling Co. 457
Address R.Rt. 4, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Russell, ss.
Spector Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 66

My commission expires Dec. 1, 1968
Elsie Coady Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- FELDMAYTAG & COMPANY
Farm- Fisher No. 2

SEC. 29 T. 1 R. 18W
C SW NW

Total Depth. 3630'
Comm. 2/17/60 Comp. 2/28/60
Shot or Treated.
Contractor. Leben Drilling, Incorporated
Issued. 5/28/60

County Phillips
KANSAS



15-147-00414-00-00

CASING:
8 5/8" 227' w/150 sks.
4 1/2" 3632'

Elevation. 2202 RB

Production. 25 BOPD

Figures indicate Bottom of Formations.

surface clay	20
sand	60
shale	227
shale & shells	350
shale, sand & shells	1215
shale	1790
anhydrite	1820
shale & shells	1880
shale & lime	2920
lime	3070
lime & shale	3175
lime	3238
shale & lime	3395
lime	3630
Total Depth	

TOPS: SCOUT	
Heebner	3355
Toronto	3385
Kansas City	3401
Base Kansas City	3611

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1966

CONSERVATION DIVISION
Wichita, Kansas