

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 4-5

15-147-00729-00-00

LOCATION SW SE NW

SEC. 28 TWP. 1 RGE. 18 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 6-1 Lease Jackson "C"

Operator Prugh Pet Co Address 907 Kennedy Bldg Tulsa, Okla

Field _____ County Phillips

Total Depth 3478 Feet.

Plugging Contractor R & D Pipe Pulling

Plugging Contractor's License No. 236

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 187' circulated with cement - 5 1/2" at 3475' with

150 sax cement behind - P.B. to 3440' - Perforated at 3398'.

Filled with sand to 3380', set 4 sax cement with dump bailer,

pulled 1210' 5 1/2" - mud to 187', set rock and 15 sax cement,

mud to 35', set rock and 10 sax cement to bottom cellar.

District Conservation Agent

Date 10-3-55

OCT 6 - 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 28 T 1 R 18 W
BOOK PAGE 4 LINE 5