

9

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don H. Peaker Et al 15-147-20065-00-00

Complete Address: P.O. BOX 1595 Pueblo, Colorado

Lease Name Goddard Well No. 1

Location NE NE SW Sec. 29 Twp. 1 Rge. (E) (W)18

County Phillips Total Depth 3655

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Red Tiger Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 1A Day ~~17~~ 18 Month 3 Year 1969

The Above well was plugged as follows:

RTD 3655: 8 5/8 csg set at 221' cwc. Cmt Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 1100' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Wessley
Well Plugging Supervisor

INVOICED

DATE 3-21-69

INV. NO. 9487-W