

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 23 1966

CONSERVATION DIVISION  
Wichita, Kansas

15-147-00123-00-00

Operator's Full Name Specter Pipe & Supply, Inc.

Complete Address: Box 169 Russell, Kansas

Lease Name Federal Farm Mortgage Well No. 1

Location NW NW SW Sec. 29 Twp. 1 Rge. 18 (E) (W) X

County Phillips Total Depth 3682'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ralph Lynch Casing Pulling Co.

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 4: P Day 20 Month 9 Year 1966

The Above well was plugged as follows:

Total Depth 3682' 8 5/8 csg set at 225' cwc 150 sc.

5 1/2 csg set at 3682' cw 150 sc cement.

Plug at 3350' Sand back to 3300' dumped 5 sc cement with dump bailer.

Circulated 15 sc gel mud at 600'.

Set 25 sc cement plug at 540'.

Mud to 225' set 20 sc cement plug.

Mud to 40' set plug, 10' rock and 10 sc cement to base of celler.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/26/66  
INV. NO. 3999-a

Signed: [Signature]  
Well Plugging Supervisor