

**KANSAS
STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1966

15-147-00414-00-00
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address: Box 169 Russell, Kansas

Lease Name Fischer Well No. 2

Location C SW NW Sec. 29 Twp. 1 Rge. 18 (E) (W) X

County Phillips Total Depth 3630'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Lynch Casing Pulling Co.

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 2:30 P Day 18 Month 9 Year 1966

The Above well was plugged as follows:

Total Depth 3630' 8 5/8 csg set at 3630' cwc 150 sc. cement

4 1/4 csg set at 3630' cw 150 sc. cement

Plug 3350' sand back to 3300' dumped 4 sc cement with dump bailer.

Circulated 15 sc gel mud at 600'

Set 25 sc cement plug at 540'

Mud to 225'-Set 20 sc cem. plug.

Mud to 40' set 10' rock and 10 sc. cem. to base of celler.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/20/66

INV. NO. 3950-a

Signed: Red Messing
Well Plugging Supervisor