

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

15-147-00737-00-09 FILE NO. 10-6

LOCATION SE NE NE

SEC. 29 TWP. 1 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Davis

Operator Geo Herman Kaiser Address 909 Palace Bldg Tulsa, Okla

Field _____ County Phillips

Total Depth 3518 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" 251' circulated with cement - 5 1/2" 3517' with 125 sax
cement behind - P. B. to 3482' - perforated 3429'

Filled with sand to 3419', set 4 sax cement with dump bailer,
pulled 1316' 5 1/2" - pumped hole full commercial mud (40 sax Gel),
displaced 35 sax cement through 5 1/2" at 660', heavy mud to 45',
set rock and 15 sax cement to bottom cellar.

Mudding and Cementing by Sun Cementing Co.

E. J. Petty
District Conservation Agent

Date 5-24-57

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1957 May 28, 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 29 T 1 R 18 W
BOOK PAGE 10 OF 6