

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

15-147-01008-00-00
API Number 15 - - (of this well)

Operator's Full Name LADD PETROLEUM CORPORATION
Complete Address 830 DENVER CLUB, BLDG, DENVER, COLORADO 80202
Lease Name DAVIS Well No. "B" #1
Location w 1/2 - E 1/2 - SE Sec 29 Twp. 1 Rge. 18 (E) (W)
County PHILLIPS Total Depth 3666 FT
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated

Plugging Contractor GLENN'S CASING PULLING, INC.
Address BOX 413 - ELLENWOOD, KANSAS 67526 License No. 832
Operation Completed: Hour 11:10 AM Day 6th Month MAY Year 1980

The above well was plugged as follows:
8 5/8" 221^{EF} SR CUC w/175ST = 4 1/2" SET AT 3663^{EF} w/250ST CMT.
PLUG. BACK TO 3633^{EF} TOP OF PERFS 3468^{EF}
BOTTOM SANDED AND 4ST CMT TO 3400^{EF} - SHOT PIPE 5 TIMES
RECOVERED 1207^{EF}
ORDERED 135ST 50% POZMIX 6% GEL -> 17ST GEL -> 5ST HULL'S -> 8 5/8" PLUG.
PAT IN -> 3ST HULL'S -> 5ST GEL -> 65ST CMT. -> 12ST GEL.
2ST HULL'S -> RELEASED PLUG. AND 70ST CMT.
MAX PRESSURE 300^{PSI} -> CEMENTED BY ALLIED CMT.

I hereby certify that the above well was plugged as herein stated.

Signed: Walter Schmidt
Well Plugging Supervisor
MAY 9 1980

INVOICED
DATE 5-7-80
INV. NO. 2116-w