

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-08283-00-00

Spot: N2S2SW

Sec/Twnshp/Rge: 25-14S-15W

4290 feet from N Section Line, 1320 feet from W Section Line

Lease Name: HARBAUGH B

Well #: 2

County: RUSSELL

Total Vertical Depth: 3180 feet

Operator License No.: 31250

PROD Size: 6 feet: 3174

Op Name: HUXMAN, RICHARD LEON DBA KSC O

SURF Size: 10.75 feet: 782

Address: PO BOX 567

RUSSELL, KS 67665

103³⁵

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/02/2004 1:30 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVID FUNK

Company: QUALITY WELL SERVICE, INC.

Phone: (785) 483-3854

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/02/2004 3:30 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran 1" to 600'.
Circulated with 70 sxs cement.
POOH.
Tied onto 5 1/2" and pumped 180 sxs cement with 500# hulls.
Max. P.S.I. 400#. S.I.P. 100#.

Top	Bot	Thru	Comments
3177	3180		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

RECEIVED

MAR 09 2004

KCC WICHITA

INVOICED

DATE

3-15-04

INV. NO.

2004061275

Form CP-2/3

MAR 05 2004

H.H. BLAIR

#9

HARBAUGH

QW 2 52 SW


25-14-15 W

Contr:

RUSSELL

E 1765 Comm 9-19-40 Comp. 11-3-40 IP 3132 BO

Tops	Depth	Datum	Casing
			8" 2522
ANHY	770		7" 2945
			6" 3174
TOP	2660		
DODGE	2900		
LANE	2935		
CONG	3171		
ARB	3174		
TD	3180		

3100' OIH/6 hrs
SO 3177 $\frac{1}{2}$ INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

23010701