

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-08260-00-00
Spot: NWNESW Sec/Twnshp/Rge: 25-14S-15W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HARBAUGH B Well #: 5
County: RUSSELL Total Vertical Depth: 3158 feet

Operator License No.: 31250
Op Name: HUXMAN, RICHARD LEON DBA KSC O
Address: PO BOX 567
RUSSELL, KS 67665

PROD Size: 6 feet: 3149
SURF Size: 10.75 feet: 760

\$102⁶⁴

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/02/2004 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID FUNK Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-3854

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2004 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1425' and 770'.
Pumped 50 sxs 60/40 pozmix - 10% gel cement with 200# hulls, followed with 19 sxs gel with 300# hulls, followed with 100 sxs cement.
Max. P.S.I. 800#. S.I.P. 100#.
Tied onto 7" - 10 3/4" annulus and pumped 120 sxs cement with 100# hulls.
Cement circulated up 5 1/2" - 7" annulus.

Perfs:

Top	Bot	Thru	Comments
2948	2956		
2940	2944		
2927	2932		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

RECEIVED

MAR 09 2004

KCC WICHITA

INVOICED

DATE

3-15-04

INV. NO.

2004061275

MAR 05 2004

HARTMAN-BLAIR OIL

#5

HARBAUGH

25-14-15W
NW NE, SW

Contr.

RUSSELL

County

E 1746 Comm 5-10-37 Comp. 6-30-37 IP 1312 BOPD

Tops	Depth	Datum
ANHY	753	+993
LANS	2910	
ARB	3148	
GORH	3156	
TD	3158	

Casing

12" 465

8" 2497

6" 3149

SO 2928-32, 2935-42

1½ BOPH 3051-62

2000+ OTH/1½ hrs

A/4000

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

+	+	+
+	+	+
+	+	+