

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20924-00-00
Spot: E2W2NW Sec/Twnshp/Rge: 33-15S-13W
3960 feet from S Section Line, 4290 feet from E Section Line
Lease Name: CHRISTIANS Well #: 2
County: RUSSELL Total Vertical Depth: 3357 feet

Operator License No.: 31250
Op Name: HUXMAN, RICHARD LEON DBA KSC O
Address: PO BOX 567
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3351 w/100 sxs cmt
SURF Size: 8.625 feet: 299 w/250 sxs cmt

4109¹⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2004 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID FUNK Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-3854

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS
Date/Time Plugging Completed: 02/26/2004 10:00 AM

Witness Type: COMPLETE (100%)
KCC Agent: CASE MORRIS

Actual Plugging Report:

Drilled to 540' with power swivel. Not making any progress.
Pumped 50 sxs 60/40 pozmix - 10% gel down backside.
Max. P.S.I. 300#. S.I.P. 100#.
Circulated cement from 500' with 40 sxs cement.
POOH.
Tied onto casing and pumped 180 sxs cement with 400# hulls.
Max. P.S.I. 400#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3277	3280		
3165	3169		
3127	3132		
3104	3110		

RECEIVED
MAR 05 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

INVOICED

DATE 3-15-04
INV. NO. 2004061275

(TECHNICIAN)

MAR 03 2004

GUSHER, INC. #2 CHRISTIANS 33-15-13W
 BOX 240 1200' FNL &
 HOLDREGE, NEB. 990' FWL, NW
 CONTR RED TIGER DRLG. CO. CTY RUSSELL

GEOL _____ FIELD TRAPP

E 1900 RB CM 7/2/76 CARD ISSUED 8/12/76 IP P 20 BOPD + 80 BWPD
 ARB 3351-57

+	+
+	+
+	+
+	+

API 15-167-20,924

SMP	TOPS	DEPTH	DATUM
1ST TARKI	D SD		
		2450	- 550
2ND TARKI	D SD		
		2464	- 564
HEEB		3009	-1109
KC		3093	-1193
ARB		3342	-1442
OTD		3357	-1457
AWH			499d

8 5/8" 299/250sx, 5 1/2" 3351/100sx
 NO LOG
 DST (1) 2438-2500/1', 75' WM, SIP 708-
 636#, FP 63-90#
 DST (2) 3104-3175/1', 100' M W/ OIL SP,
 150' WM W/OIL SPKS, 150' MW, SIP 629-
 609#, FP 54-251#
 DST (3) 3332-3349/1', 10' M, SIP 54#,
 FP 9-11#
 DST (4) 3335-3357/1', 1105' FL (460' HO &
 GCM, 445' OILY, GSY, MW) 200' W, SIP
 1085-1085#, FP 76-461#
 MICT - CO TD, SWB DWN

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS