

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-08285-00-01
Spot: S2NWSW Sec/Twnshp/Rge: 25-14S-15W
3300 feet from N Section Line, 660 feet from W Section Line
Lease Name: HARBAUGH Well #: 10
County: RUSSELL Total Vertical Depth: 3189 feet

Operator License No.: 31250
Op Name: HUXMAN, RICHARD LEON DBA KSC O
Address: PO BOX 567
RUSSELL, KS 67665

PLG Size: feet: 3100
PROD Size: 7 feet: 3185 100 SX CMT
SURF Size: 10.75 feet: 805 12 SX CMT

#10364

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2004 5:15 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID FUNK Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-3854

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2004 6:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1450' and 810'.
Tied onto 4 1/2" and pumped 50 sxs 60/40 pozmix - 10% gel cement with 200# hulls,
followed by 19 sxs gel with 300# hulls, followed with 270 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3005	3008		
2971	2975		
2960	2965		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Case Morris*
(TECHNICIAN)

110
RECEIVED INVOICED INVOICED
MAR 09 2004 DATE 3-15-04
KCC WICHITA INV. NO. 2004061275

Form CP-2/3

MAR 05 2004

replacement card

PRODUCERS OIL: CO
TULSA OK 74103

25-14S-15W
C S/2 NW SW

10 HARBAUGH OWWO

site: 4-3/4 S & 4 E OF GORHAM KS
contr: UNKNOWN

cty: RUSSELL
field: GORHAM

API 15-167-08285

dr date	spd date	drig comp	card issued	last revised
02/22/83	11/15/82	11/15/82	02/24/83	03/15/99

ELV: 1768 GL LOG
 tops.....depth/datum
 ANH.....796 + 972
 TOR.....2907 -1139
 LANS.....2949 -1181
 GORHAM SD3185 -1417
 RTD OLD3189 -1421

IP status
 OIL, P 6 BO & 87.6 BWPD, PENN 3184-3189, 12/17/82
 INFO RELEASED: 3/15/99 - WAS OIL WELL - TEMP
 COMP
 OLD INFO: OPERATOR WAS HARRY GORE, 10
 HARBAUGH, SPD 06/05/49, 08/12/49 10-3/4" 805, 7"
 3185, OIL, P 80 BOPD, NW, PENN 3185-3189, 08/19/49
 (CARD ISSUED 08/26/49)
 CONTR: HARRY GORE
 COMMENT: WAS API 10G-54772
 SHOWS: 2960-2965 (LM, SO), 2971-2975 (LM, SLI SO),
 3000-3005 (LM, SO), 3184-3185 (SDY LM, FU 100' FL/30")

DRLR SD ZNS: 70-80, 170-190, 275-285, 315-330, 345-405, 3185-3189

SALT ZNS: 1230-1235, 1235-1275 (BRKN), 1275-1360

WTR ZNS: 50-55 (SDY SH, 1 BWPH), 99-100 (SH, 10 BWPH), 170-180 (SD, 5 BWPH), 180-190 (SD, HFV), 345-360 (SD, WTRY), 445-450 (REDRK, HFV), 839-840 (SH, 2 BWPH, SQZ'D, W/150 SX GMT), 2007-2014 (LM, BRKN, 1/2 BWPH)

NO CORES OR DSTS

MICT - CO, (GORHAM SD OH), SWB DWN, GSO, NAT, POP, P 80 BOPD, NW, 8/19/49

NEW INFO: FR 02/22/83, RE-ENTERED 11/15/82 WSH DWN TO 3189, DC 11/15/82 CSG: PROD CSG ALREADY IN HOLE

COMMENT: ADD'L RECOMMENDED ZNS TO TEST IN KC - 2960-2965, 2971-2975, 3005-3008

PROD DECL, OFF PMP 11/15/82, MICT - CO (GORHAM SD), SCRAPPED CSG FROM SURF TO 2750, CO FROM 2750-2878, SWB DWN & REC 3.9 BFPH (6% OIL), NAT, POP, P 6 BO & 87.6 BW/24 HRS, GSTSM, 12/17/82, (POSS KC PAY BEHIND PIPE)

PRODUCERS OIL COMPANY