

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22089-00-00
Spot: SESESE Sec/Twnshp/Rge: 18-16S-13W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: LUERMAN Well #: 6
County: BARTON Total Vertical Depth: 3435 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S. WEBB RD., STE 100
WICHITA, KS 67207

PROD Size: 4.5 feet: 3434 150 SX CMT
SURF Size: 8.625 feet: 325 185 SX CMT

A 111 64

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2004 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: GARY YOUNGER Company: YOUNGER ENERGY COMPANY Phone: (316) 681-2542

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 02/27/2004 3:15 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3333' and dumped 4 sxs cement.
Cut casing at 1500' - not loose.
Pumped 50 sxs 60/40 pozmix - 10% gel with 200# hulls.
Cut casing at 900' - not loose.
Cut casing at 600' - not loose.
Pumped 75 sxs cement with 200# hulls.
Cut casing at 250'.
Circulated with 50 sxs cement.
Pulled 250' pipe.

RECEIVED
MAR 0 8 2004
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3420	3421		
3388	3389		BP @ 3414'

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Case Morris*
(TECHNICIAN)

INVOICED
3-15-04
2004061287

MAR 0 4 2004

H-30 INC
 251 N WATER #10 #6 LUERMAN 18-16-13W
 WICHITA, KS 67202 SE SE SE
 CONTR COMPANY TOOLS CTY, BARTON

GEOL _____ FIELD TRAPP

E 1951 KB CM 9/20/80 CARD ISSUED 12/4/80 IP P 20 BOPD &
 15% WTR
 API 15-009-22,089 ARB 3388-89

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
ANH		936	+1015
HOW		2761	- 810
TOP		2840	- 889
HEEB		3072	-1121
BR LM		3149	-1198
ARB		3374	-1423
ARB DOL		3384	-1433
RTD		3435	-1484
LOGGED			

8 5/8" 325/185sx; 4 1/2" 3434/150sx
 NO DSTS
 MICT - CO, PF (ARB) 3388-89, SWB GSO
 NAT, POP, P 20 BOPD & 15% WTR

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

15-009-22,089
 12/4/80
 15% WTR
 ARB 3388-89