

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21985-00-01
Spot: SESWSW Sec/Twnshp/Rge: 12-14S-15W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: MILLS Well #: 1
County: RUSSELL Total Vertical Depth: 3338 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 804, LB 30
DALLAS, TX 75205

CIBP Size: feet: 3250
PROD Size: 4.5 feet: 3333 150 SX CMT
SURF Size: 8.625 feet: 514 280 SX CMT

\$108⁴⁹

Well Type: EOR UIC Docket No: E27568.1 Date/Time to Plug: 03/08/2004 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2004 11:45 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2880' and dumped 4 sxs cement.
Cut casing at 1400' and 900'. Did not come free.
Pumped 75 sxs 60/40 pozmix - 10% gel cement.
Cut casing at 440' - 310' - 250'.
Circulated cement from 250' with 75 sxs cement.
Pulled 250' casing.

Perfs:

Top	Bot	Thru	Comments
3210	3216		
3192	3196		
3110	3123		
3068	3071		
3057	3059		
3032	3038		
2926	2929		CIBP @ 3250'

RECEIVED
MAR 11 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris

(TECHNICIAN)
INVOICED
DATE 3-15-04
INV. NO. 2004061282

Form CP-2/3

MAR 08 2004

MAIL OIL OPER
RUSSELL KS 67665-0033

12-14S-15W
230'W, C SE SW SW

1 MILLS OWWO

str: 2-1/4 S & 3-3/4 W OF RUSSELL KS	cty: RUSSELL	API 15-167-21985
contr: RAPID WELL SVC	flld: GORHAM	
gcd: NONE		
fr date 12/21/98	spd date 09/14/98	drig comp 09/14/98
	card issued 12/21/98	last revised 12/21/98

ELV: 1868 KB LOG

tops.....	depth/ datum
ANH.....	898 + 970
TOP.....	2750 -882
HEEB.....	2974 -1106
TOR.....	2992 -1124
LANS.....	3028 -1160
PBTD.....	3236 -1368
BKC.....	3259 -1391
ARB.....	3275 -1407
LTD.....	3304 -1436
RTD OLD.....	3338 -1470

IP status:
 INJ, SHAW 2926-2929, LKC 3032-3216 OA, 09/25/98
 NOTE: CORRECTION 12/21/98 - CORR CSG
 OLD INFO: OPERATOR WAS DRISCOLL LEASE OPER,
 1 MILLS, SPD 08/30/82, 09/10/82 8-5/8" 514 / 280 SX, 4-
 1/2" 3333 / 150 SX, OIL, P 25 BOPD, NW, ARB 3283-3295
 OA, 09/26/82 (CARD ISSUED 01/20/83.)
 CONTR: REVLIN DRILLING
 GEOL: ROY KRUEGER
 NO CORES OR DSTS
 MICT - CO, PF (ARB) 8/3283-3285, SO, NAT, PF (ARB)
 8/3291-3293, AC 250 GAL, SO, RE-PF (ARB) 8/3292.5-
 3294.5, SO, POP, IPP 25 BOPD, NW, 9/26/82

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

MAIL OIL OPER,
RUSSELL KS 67665-0033

12-14S-15W
230'W, C SE SW SW

1 MILLS OWWO

1 WORKOVER:
 OPERATOR WAS DRISCOLL LEASE OPER # 1 MILLS OWWO REWORKED 01/11/83, 01/11/83
 OIL, LKC 3110-3216 OA, ARB 3283-3295 OA, 01/12/83 (CARD ISSUED 01/17/83)
 CONTR: UNKNOWN
 GEOL: NONE
 OFF PROD, MICT - CO, PF (LKC) 3192-3196, 3210-3216, W / 4 SPF, AC'D, SO, PF (LKC) 1/3110,
 1/3123, AC'D, SO, POP, OIL WELL (POTENTIAL NOT RPTD), 1/12/83, COMMINGLED W/OLD
 PAY (ARB 3283-3294.5)

2 WORKOVER:
 OPERATOR WAS DRISCOLL LEASE OPER # 1 MILLS OWWO REWORKED 01/16/84, 01/16/84
 OIL, WAB 2626-2629, LKC 3032-3216 OA, ARB 3283-3295 OA, 01/17/84 (CARD ISSUED 01/19/84
)
 CONTR: UNKNOWN
 GEOL: NONE
 OFF PROD, MICT - CO, PF (LKC) 3032-3038, 3054-3057, 3068-3071, W / 4 SPF, AC'D, SO, PF
 (WAB) 2626-2629, W / 4 SPF, AC'D, SO, POP, OIL WELL (POTENTIAL NOT RPTD), 1/17/84,
 COMMINGLED W/OLD PAYS (LKC 3110-3216 OA & ARB 3283-3294.5)
 NEW INFO: FR 12/21/98, REWORKED 09/14/98 DC 09/14/98 OFF PROD, MICT - CO, SET CIBP
 AT 3250, PB 3236 W/75 SX CMT, PF (PLATTSM) 2926-2929, W / 4 SPF, AC'D, SET 2-3/8" TBG &
 PKR AT 2879, CONVERTED TO WIW - INJECTION RATE SATISFACTORY, 9/25/98 (INJ INTO
 PLATTSM & LKC ONLY)

233.00001
 ITSO
 01.17