

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-30637-00-01
Spot: NENENW Sec/Twnshp/Rge: 28-14S-19W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SUNLEY OWWO Well #: 2
County: ELLIS Total Vertical Depth: 3837 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: 1601 BLAKE STREET, SUITE 500
DENVER, CO 80202

PROD Size: 4.5 feet: 3808 100 SX CMT
SURF Size: 8.625 feet: 206 135 SX CMT

124⁷⁰

Well Type: SWD UIC Docket No: D26512.0 Date/Time to Plug: 03/08/2004 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC.
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 737-3242

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Open hole 3808' - 3837'.
Stage collar at 1484' w/500 sxs.
Casing leak at 3002' - 3085' squeezed with 150 sxs - 2488' - 2550' squeezed w/125 sxs - 687' - 717' squeezed w/30 sxs.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2004 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Allied Cementing tied onto backside and pumped 10 sxs 60/40 pozmix with 50# hulls.
Max. P.S.I. 400#. Cement came around into 4 1/2" casing. Shut in backside.
Fisher Well Service RIH with tubing to 2100'.
Allied Cementing tied onto tubing and pumped 110 sxs 60/40 pozmix with 300# hulls mixed in - circulated cement into pit.
Fished pulled tubing. Allied tied onto 4 1/2" casing with a swedge and pumped 155 sxs 60/40 pozmix with 150# hulls mixed in.
Max. P.S.I. 400#. S.I.P. 150#.

RECEIVED
MAR 11 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed *[Signature]*
(TECHNICIAN)

INVOICED

DATE 3-15-04

INV. NO. 2004061272

Form CP-2/3

MAR 08 2004

N-B COMPANY, INC.

P. O. BOX 506

#2 SUNLEY 'OWWO'


28-14-19W
NE NE NW

RUSSELL, KS 67665

CONTR EMPHASIS OIL OPERATIONS CTY ELLIS

GEOL _____ FIELD KRAUS

ELV 2215 KB SPD _____ CARD ISSUED 10/18/84 IP ABD LOC



API NOT ASSIGNED

SMP	Tops	Depth/Datum
ANH	1482+ 733
TOP	3237-1022
HEEB	3456-1241
LANS	3500-1285
BKC	3745-1530
MARM CHT	3785-1570
MARM SD	3796-1581
ARB	3807-1592
RTD	3815-1600

GLD INFO: OPERATOR WAS FRONTIER OIL COMPANY, #4 SUNLEY 'TWIN', SPD 8/12/65, SET 8 5/8" 206/135 SX, 4 1/2" 3809/400 SX, STAGE COLLAR 1484/500SX, COMP. AS P 25 BOPD, NW, ARB OH 3809-15, 10/12/65, (CARD ISSUED 10/12/65), CONTR: RED TIGER DRILLING COMPANY

DST (1) 3229-50 (TOP) / OP 45", REC 300' MUD, 600' SW, FSIP 300#, FP NA

DST (2) 3515-36 (LKC) / OP 120", REC 900' SW, FSIP 500#/30", FP 80-500#

DST (3) 3542-55 (LKC) / OP 30", WB 12", REC 5' MUD, SIP 0-0#, FP 0-0#

DST (4) 3564-74 (LKC) / OP 120", REC 500' MW, SIP 940#, FP 300-500#

DST (5) 3621-44 (LKC) / OP 60", WB 43", REC 315' MUD, FSIP 590#/30", FP 0-0#

DST (6) 3646-90 (LKC) / OP 120", WB, REC 120' WM, FSIP 860#/30", FP 0-180#

(over)

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS